

Subdivisional Lines, T.1 S.,R.35 E.,W.M.

Chains		Feet
	<p>Land; mountainous and covered with timber, 85.84 chs. Good pine and tamarack timber on table land. Soil; 3rd rate.</p>	
	<p>General Description</p>	
	<p>General description of Tp. consists chiefly of rolling land with small draws, running to the Meacham Creek on the East and Mc Kay on the South and West.</p> <p>Secs. 29, 30, 31 & 32 and part of Sec. 19 are very rough, being cut up by McKay Creek and canyons running into it.</p> <p>There is pine, fir, tamarack and spruce timber, over nearly the whole Tp., but very scattering in places and on the whole of little value.</p> <p>There is good grass, where timber and underbrush is not too thick.</p> <p>Water is very scarce late in the summer.</p> <p>Soil in places, 1st rate, but is generally rocky and will average about 2nd rate.</p> <p style="text-align: right;">July 3rd, 1887.</p>	
	<p>Resurvey Portion of N. Bdy. of T.2 S.,R.35 E.,W.M. As surveyed by L.E.Wilkes,U.S.Deputy Surveyor, Under Special Instructions, Group 29 Dated Feb.20, 1917.</p>	
	<p>From the Cor.of Tps.1 & 2, Rs.34 & 35 E., E. retracing the N. Bdy. of Sec.6; at 39.79 chs. fall 11 lks. S.of the $\frac{1}{4}$ Sec. Cor.; at 48.81 chs. fall 70 lks. S. of the Closing Cor.of Secs. 31 & 32,T.1 S.,R.35 E., and at 76.43 chs. fall 90 lks. S. of the Closing Cor. of Secs. 6 & 32 on E. Bdy. of the Umatilla Indian Reservation.</p>	
	<p>The Closing Cor. of Secs. 6 & 32 on the E. Bdy. of the Umatilla Indian Reservation is a badly decayed post, marks nearly illegible; therefore; at the exact point Set an iron post, 3 ft. long, 2 ins. diam.,24 ins.in the</p>	