

Exteriors T.1 S., R.37 E., W.M.

Chains		Feet
	<p>post (which I reset and raised mound of stone about base) 4 ft. long, 4 ins. sq., 1 ft. in ground, marked T.1 S., S.31 on N.E. R.37 E., S.6 on S.E. T.2 S., S.1 on S.W. and R.36 E., S.36 on N.W. faces, from which, A pine, 15 ins. diam., brs. S.73½°W., 274 lks. dist., marked T.2 S., R.36 E., S.1, B.T. A pine, 30 ins. diam., brs. S.41½°E., 390 lks. dist., marked T.2 S., R.37 E., S.6, B.T. A pine, 10 ins. diam., brs. N.26°E., 180 lks. dist., marked T.1 S., R.37 E., S.31, B.T.</p> <p>I run N. bet. Secs. 31 & 36. Var. 21°E.</p>	
10.00	Descend through dead and fallen timber.	
21.50	Ascend	
25.00	Summit of point, 200 ft. above ravine. Descend.	
31.50	Bottom of ravine, course W. Ascend.	
40.00	<p>Set post, 3½ ft. long, 3 ins. sq., 18 ins. in ground on S. hillside, 150 ft. above bottom of ravine, in open tim- ber for ¼ Sec. Cor., marked ¼ S. on E. & W. faces, from which, A pine, 18 ins. diam., brs. S.89°W., 10 lks. dist., marked ¼ S., B.T.</p> <p>No other trees in limits and raised mound of stone along- side.</p>	
45.00	Descend through open timber. Summit of ridge, course W.	
61.00	Ascend rocky mountain side.	
80.00	<p>A pine tree, 6 ins. diam., which I marked for Cor. to Secs. 25, 30, 31 & 36, in open timber on S. slope of hill, marked, T.1 S., S.30 on N.E. R.37, S.31 on S.E. R.36, S.36 on S.W. and S.25 on N.W. faces with</p>	