

## Exteriors of T. 1 S., R. 37 E., W.M.

Chains	Feet
	with an X on top for Cor. to Secs., 13, 18, 19 & 24, marked
	T.1 S., S.18 on N.E.
	R.37 E., S.19 on S.E.
	R.36 E., S.24 on S.W. and
	S.13 in the N.W. angles of X, from which,
	A fir, 8 ins. diam., brs. S.26°E., 23 lks. dist., marked T.1 S., R.37 E., S.19, B.T.
	A fir, 10 ins. diam., brs. S.84°W., 40 lks. dist., marked T.1 S., R.36 E., S.24, B.T.
	A fir, 10 ins. diam., brs. N.86°E., 56 lks. dist., marked T.1 S., R.37 E., S.18, B.T.
	A fir, 5 ins. diam., brs. N.10°W., 31 lks. dist., marked T.1 S., R.36 E., S.13, B.T.
	Land; rough, mountainous and broken.
	Soil; gravelly, 4th rate.
	Timber, pine and fir.
	N. bet. Secs. 13 & 18.
	Var. 19°30'E.
	Descend abruptly.
16.50	Cross rocky bald point.
27.00	Descend.
40.00	A fir, 10 ins. diam., on steep N. mountainside, 200 ft. above creek, in young fir timber, which I marked for $\frac{1}{4}$ Sec. Cor., $\frac{1}{4}$ S. on the E. & W. faces, from which,
	A fir, 4 ins. diam., brs. N.28°W., 11 lks. dist., marked $\frac{1}{4}$ S., B.T.
	A fir, 12 ins. diam., brs. S.29°E., 9 lks. dist., marked $\frac{1}{4}$ S., B.T.
	Descend Var. 18°50'E.
43.00	Bottom of ravine, course W. Ascend.
70.50	Through open glade.
75.00	Heavy pine timber and undergrowth.
80.00	Set post, $4\frac{1}{2}$ ft. long, 4 ins. sq., 2 ft. in ground, with mound of stone around it, $3\frac{1}{2}$ ft. base, 18 ins. high, on