

Exteriors of T. 1 S., R.37 E., W.M.

Chains	Feet
	<p>S.1 on N.W. faces, with 5 notches on S. and 1 notch on N. edges, from which, A pine, 4 ins. diam., brs. N.45°E., 5 lks. dist., marked T.1 S., R.37 E., S.6, B.T. A pine, 7 ins. diam., brs. S.80°E., 7 lks. dist., marked T.1 S., R.37 E., S.7, B.T. A pine, 12 ins. diam., brs. S.66°W., 15 lks. dist., marked T.1 S., R.36 E., S.12, B.T. A pine, 10 ins. diam., brs. N.19°W., 21 lks. dist., marked T.1 S., R.36 E., S.1, B.T.</p> <p>Land; high, broken and mountainous. Soil; rocky, 4th rate. Timber, pine, fir and tamarack.</p>
	<p>N. bet. Secs. 1 & 6. Var. 20°30'E.</p>
10.00	Descend through forests of black pine.
39.00	A spring branch, course E. Ascend.
40.00	Set post, 3½ ft. long, 3 ins. sq., 15 ins. in ground, on N. side of ravine, 20 ft. above spring branch, in dense timber, for ¼ Sec. Cor., marked ¼ S. on E. & W. faces, from which, A tamarack, 14 ins. diam., brs. S.24°W., 5 lks. dist., marked ¼ S., B.T. A spruce, 8 ins. diam., brs. S.11°E., 16 lks. dist., marked ¼ S., B.T.
49.00	Gradual descent.
75.00	Intersect the Base Line, 21.90 chs. E. of Cor. to Tps. 1 N. Rs.36 & 37 E. Set post, 4½ ft. long, 4 ins. sq., 24 ins. in ground for Closing Cor. to Tps. 1 S., Rs.36 & 37 E., marked, C.C., T.1 S. on S. R.37 E., S.6 on E. R.36 E., S.1 on W. faces, with 6 notches on S.E. & W. faces, from which,