

## Exteriors of T. 1 S., R. 37 E., W.M.

Chains		Feet
18.00	Descend through dead & fallen timber.	
30.00	Ascend.	
34.00	Top of hill and descend, 200 ft. high.	
40.50	Bed of ravine, 200 ft. deep	
48.57	The $\frac{1}{4}$ Sec. Cor.	
54.00	Top of ridge, course E.	
70.00	Ascend hill.	
80.00	<p>Set basalt stone, 18 x 8 x 7 ins., 12 ins. in ground, for Cor. to Secs. 30 &amp; 31, marked with 5 notches on N. and 1 on S. edges; from which,</p> <p>A pine, 12 ins. diam., brs. S.33°E., 76 lks. dist., marked R.37 E., S.31, B.T.</p> <p>A pine, 36 ins. diam., brs. N.83°E., 39 lks. dist., marked T.1 S., S.30, B.T.</p> <p>A fir, 18 ins. diam., brs. N.68°W., 76 lks. dist., marked R.36 E., B.T.</p> <p>Land; broken and mountainous.</p> <p>Soil: 3rd rate.</p> <p>Timber; pine and fir.</p>	
	<p>N. on W. Bdy. of Sec. 30</p> <p style="text-align: right;">Var. 20°30'E.</p>	
9.09	<p>The Cor. to Secs. 25, 36, 30 &amp; 31; which is a pine, 6 ins. diam., marked</p> <p style="text-align: center;">T.1 S., S.30 on N.E.</p> <p style="text-align: center;">R.37 E., S.31 on S.E.</p> <p style="text-align: center;">R.36 E., S.36 on S.W. and</p> <p style="text-align: center;">S.25 on W. faces, from which,</p> <p>A pine, 8 ins. diam., brs. N.63°W., 43 lks. dist., marked T.1 S., R.36 E., S.25, B.T.</p> <p>A pine, 18 ins. diam., brs. S.80°W., 43 lks. dist., marked T.1 S., R.36 E., S.36, B.T.</p> <p>A pine, 20 ins. diam., brs. S.34 °E., 46 lks. dist., marked T.1 S., R.37 E., S.31, B.T.</p> <p>Destroyed marks referring to Secs. 30 &amp; 31.</p>	
49.55	The $\frac{1}{4}$ Sec. Cor.	