

## Exteriors of T. 1 S., R. 37 E., W.M.

Chains		Feet
	<p>marked T.1 S., S.18, B.T.</p> <p>A fir, 18 ins. diam., brs. S.34°E., 70 lks. dist., marked R.37 E., S.19, B.T.</p> <p>A pine, 18 ins. diam., brs. S.10°W., 80 lks. dist., marked R.36 E., B:T.</p> <p>Land; mountainous.</p> <p>Soil; 3rd rate.</p> <p>Timber; pine &amp; fir.</p> <p>Undergrowth of pine and willow.</p>	
	<p>N. on W. Bdy. of Sec. 18.</p> <p style="text-align: right;">Var. 19°30' E.</p>	
10.95	<p>The Cor. to Secs. 18, 19, 13 &amp; 24, which is a basalt stone, 16 x 16 x 2 ins., from which;</p> <p>A pine, 8 ins. diam., brs. S. 26°E., 23 lks. dist., marked T.1 S., R.37 E., S.19, B.T.</p> <p>A pine, 10 ins. diam., brs. S.84°W., 40 lks. dist., marked T.1 S., R.36 E., S.24, B.T.</p> <p>A pine, 10 ins. diam., brs. N.86°E., 56 lks. dist., marked T.1 S., R.37 E., S.18, B.T.</p> <p>A pine, 5 ins. diam., brs. N.10°W., 31 lks. dist., marked T.1 S., R.36 E., S.13, B.T.</p> <p>Destroyed marks referring to Secs. 18 &amp; 19.</p>	
27.50	Rocky point.	
51.40	The $\frac{1}{4}$ Sec. Cor.	
54.40	Bed of ravine, course W.	
80.00	<p>Set basalt stone, 18 x 9 x 7 ins., 12 ins. in ground for Cor. to Secs. 7 &amp; 18, marked with 4 notches on S. and 2 on N. edges, and raised mound of stone alongside.</p> <p>Pits impracticable, from which;</p> <p>A pine, 24 ins. diam., brs. S.12°E., 39 lks. dist., marked T.1 S., R.37 E., S.18, B.T.</p> <p>No other trees convenient.</p> <p>Land; mountainous.</p> <p>Soil; 3rd rate.</p> <p>Timber; pine &amp; fir. Undergrowth of pine and laurel.</p>	