

Subdivisional Lines, T.1 S., R.36 E., W.M.

Chains		Feet
71.00	Bottom of gulch, course N.	
80.52	Intersect, 30 lks. S. of Cor. to Secs. 15, 16, 21 & 22.	
	Thence I run	
	S.89°47'W. on true line bet. Secs. 16 & 21.	
40.26	Set basalt stone, 15 x 15 x 7 ins., 10 ins. in ground for	
	¼ Sec. Cor., marked ¼ on N. face, and raised mound of	
	stone alongside.	
80.52	The Cor. to Secs. 16, 17, 20 & 21.	
	Land; mountainous.	
	Soil; 2nd rate.	
	Timber; scattering fir, pine and tamarack.	
	N. bet. Secs. 16 & 17	
	Var. 19½°E.	
	Descend about 50 ft. to	
3.00	Bottom of gulch, course W.	
25.50	Top of ridge about 100 ft. above gulch, course W.	
33.00	Bottom of gulch about 75 ft. below ridge, course W.	
40.00	Set basalt stone, 16 x 9 x 7 ins., 11 ins. in ground for ¼	
	Sec. Cor., marked ¼ on W. face and raised mound of stone	
	alongside.	
42.50	Top of ridge, about 100 ft. above gulch, course W.	
64.00	Bottom of gulch, about 150 ft. below ridge; dry bed of	
	creek, course N.E.	
80.00	Set basalt stone, 24 x 10 x 6 ins., 18 ins. in ground for	
	Cor. to Secs. 8, 9, 16 and 17, marked with 4 notches on	
	S. & E. edges; from which,	
	A pine, 5 ins. diam., brs. N.60°E., 26 lks. dist.,	
	marked T.1 S., R.36 E., S.9, B.T.	
	A pine, 7 ins. diam., brs. S.85°E., 37 lks. dist.,	
	marked T.1 S., R.36 E., S.16, B.T.	
	A pine, 15 ins. diam., brs. N.70°W., 66 lks. dist.,	
	marked T.1 S., R.36 E., S.8, B.T.	
	No other tree within limits and raised mound of stone	
	alongside.	
	Land; mountainous.	