

## Subdivisional Lines, T.1 S., R.36 E., W.M.

Chains		Feet
	Soil; 2nd rate. Timber; scattering pine, fir and tamarack with dense undergrowth of buck brush. Oct. 23, 1882.	
	E. on random line bet. Secs. 9 & 16. Var. 22°E. Through timber.	
10.50	Wagon road, course N.W.	
12.50	Dry bed of Meacham creek, 150 lks. wide, course S.E.	
16.00	Leave heavy timber and ascend through scattering timber.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
49.00	Top of ridge, about 500 ft. above creek, course S.	
67.00	Bottom of gulch, about 250 ft. below ridge, course S. Ascend about 200 ft. to	
80.66	Intersect, 75 lks. S. of Cor. to Secs. 9, 10, 15 & 16. Thence I run S.89°28' E. on a true line bet. Secs. 9 & 16.	
40.33	Set basalt stone, 22 x 6 x 4 ins., 16 ins. in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, and raised mound of stone alongside.	
80.66	The Cor. to Secs. 8, 9, 16 & 17. Land; mountainous. Soil; 2nd rate. Heavily timbered with pine on W. 16.00 chs., with scattering pine on remainder.	
	N. bet. Secs. 8 & 9. Var. 22°E. Descend through timber	
15.00	Foot of hill, about 150 ft. below Cor., course S.E.	
16.00	Wagon road, course S.E.	
19.00	Dry bed of Meacham creek, 75 lks. wide, course S.E.; Leave heavy timber and ascend mountain through scattering timber.	
40.00	Set basalt stone, 14 x 10 x 4 ins., 9 ins. in ground for	