

Subdivisional Lines, T.1 S., R.37 E., W.M.

Chains		Feet
	A pine, 5 ins. diam., brs. N.80°W., 16 lks. dist., marked T.1 S., S.12, B.T.	
	Thence I run S.86°W. on a true line bet. Secs. 12 & 13	
40.37	Set basalt stone, 16 x 12 x 6 ins., in ground for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, from which, A fir, 20 ins. diam., brs. S.75°W., 31 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 6 ins. diam., brs. N.28°W., 76 lks. dist., marked $\frac{1}{4}$ S., B.T.	
80.75	The Cor. to Secs. 11, 12, 13 & 14. Land; mountainous. Soil; 2nd rate. Heavy pine & fir timber. Dense pine and fir undergrowth.	
	N. bet. Secs. 11 & 12. Var. 22°E.	
	Ascend long hillside.	
14.00	Ravine, course S.20°W.	
40.00	Set basalt stone, 18 x 10 x 6 ins., in stony ground, piled stone around Cor., marked $\frac{1}{4}$ on W. face for $\frac{1}{4}$ Sec. Cor., from which, A fir, 4 ins. diam., brs. N.82°W., 61 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 4 ins. diam., brs. N.78°E., 80 lks. dist., marked $\frac{1}{4}$ S., B.T.	
	On top of ridge, brs. E. & W., 400 ft. above Sec. Cor.	
41.00	Descend steep hill.	
79.00	Fork of Meacham Creek, 10 lks. wide, in canyon, runs W., 1500 ft. deep.	
80.00	Set basalt stone, 18 x 9 x 5 ins., 12 ins. in ground for Cor. to Secs. 1, 2, 11 & 12, marked with 5 notches on S. and 1 on E. edges, from which, A fir, 18 ins. diam., brs. N.42°E., 22 lks. dist., marked T.1 S., S.1, B.T.	