

## Subdivisional Lines, T.1 S., R.37 E., W.M.

Chains		Feet
	<p>A pine, 36 ins. diam., brs. S.17°W., 177 lks. dist., marked S.32, B.T.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine, fir and tamarack.</p> <p>Dense pine and fir undergrowth.</p>	
	***** N. bet. Secs. 28 & 29. *****	
80.18	<p>The Cor. to Secs. 28, 29, 32 &amp; 33.</p> <p>Land; mountainous.</p> <p>Soil; 2nd rate.</p> <p>Heavily timbered with pine and fir.</p> <p>Undergrowth of fir and pine.</p> <p>*****</p> <p style="text-align: right;">Sept. 25, 1882.</p>	
	N. bet. Secs. 28 & 29.  Var. 20°30'E.	
19.00	Ravine, course S.20°E.	
40.00	<p>Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground for <math>\frac{1}{4}</math> Sec. Cor., marked <math>\frac{1}{4}</math> S. on W. face, from which;</p> <p>A pine, 36 ins. diam., brs. N.41°E., 34 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p> <p>A pine, 4 ins. diam., brs. N.52°W., 68 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p>	
55.00	Ravine, course S.W.	
80.00	<p>Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 20, 21, 28 &amp; 29, marked</p> <p style="padding-left: 40px;">T.1 S., S.21 on N.E.</p> <p style="padding-left: 40px;">R.37 E., S.20 on N.W.</p> <p style="padding-left: 40px;">S.29 on S.W. and</p> <p style="padding-left: 40px;">S.28 on S.E., with 2 notches on S. and 4 on E.</p> <p>edges, from which;</p> <p>A fir, 5 ins. diam., brs. N.38°E., 8 lks. dist., marked T.1 S., S.21, B.T.</p> <p>A pine, 12 ins. diam., brs. S.31°E., 43 lks. dist.,</p>	