

Subdivisional Lines, T.1 S., R.37 E., W.M.

Chains	Feet
	<p>T.1 S., S.32 on N.E. R.37 E., S.5 on S.E. T.2 S., S.6 on S.W. and S.31 on N.W., with 1 notch on W. and 5 notches on E. edges, from which;</p> <p>A pine, 12 ins. diam., brs. N.10°E., 74 lks. dist., marked T.1 S., S.32, B.T.</p> <p>A pine, 6 ins. diam., brs. N.16°W., 59 lks. dist., marked T.1 S., R.37 E., S.31, B.T.</p> <p>A pine, 44 ins. diam., brs. S.37°E., 27 lks. dist., marked T.2 S., R.37 E., S.5, B.T.</p> <p>A fir, 18 ins. diam., brs. S.67°W., 36 lks. dist., marked T.2 S., R.37 E., S.6, B.T.</p> <p>I run N. bet. Secs. 31 & 32. Ascend Var. 21½°E.</p>
34.00	Old Emigrant wagon road, brs. N.W. & S.E., 200 ft. above Sec. Cor.
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins; in ground, for ¼ Sec. Cor., marked ¼ S. on W. face, from which; A fir, 7 ins. diam., brs. N.50°E., 11 lks. dist., marked ¼ S., B.T. A fir, 4 ins. diam., brs. S.58°W., 34 lks. dist., marked ¼ S., B.T.
80.00	Set stone, 24 x 12 x 7 ins., 18 ins. in ground for Cor. to Secs. 29, 30, 31 & 32, marked with 1 notch on S. and 5 on E. edges, from which; A pine, 5 ins. diam., brs. N.53°E., 27 lks. dist., marked T.1 S., S.29, B.T. A pine, 4 ins. diam., brs. N.20°W., 17 lks. dist., marked R.37 E., S.30, B.T. A pine, 4 ins. diam., brs. S.63°W., 12 lks. dist., marked S.31, B.T. A pine, 4 ins. diam., brs. S.10°E., 17 lks. dist., marked S.32, B.T., 300 ft. above ¼ Sec. Cor.