

## Subdivisional Lines, T.1 S., R.37 E., W.M.

Chains		Feet
	N. bet. Secs. 7 & 8.	
	Ascend from Cor. Var. 20°30'E.	
18.00	Top of ridge, brs. N.W. & S.E., 300 ft. above Secs. Cor. &	
25.00	Descend.	
40.00	Set post, 3 ft. long, 3 ins. sq.; 24 ins. in ground for $\frac{1}{4}$ Sec. Cor., 150 ft. below top of ridge, marked $\frac{1}{4}$ S. on W. face, from which, A tamarack, 20 ins. diam., brs. N. 73°W., 19 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 7 ins. diam., brs. N. 70°E., 17 lks. dist., marked $\frac{1}{4}$ S., B.T.	
69.00	Ravine, course N.W., 650 ft. below $\frac{1}{4}$ Sec. Cor.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground for Cor. to Secs. 5, 6, 7 & 8, on hillside, slopes W., marked; T.1 S., S.8 on N.E. S.7 on S.W. R.37 E., S.6 on N.W. and S.8 on S.E., with 5 notches on S. and E. edges, from which; A fir, 15 ins. diam., brs. S. 70°W., 10 lks. dist., marked S.7, B.T. A pine, 10 ins. diam., brs. N. 62°W., 27 lks. dist., marked R.37 E., S.6, B.T. A fir, 18 ins. diam., brs. N. 57°E., 13 lks. dist., marked T.1 S., S.5, B.T. A fir, 15 ins. diam., brs. S. 53°E., 19 lks. dist., marked S.8, B.T.	
	Land; mountainous.	
	Soil; 2nd rate.	
	Heavily timbered with pine and fir on N. 60 chs. Scattering pine on S. 20 chs.	
	*****	
	Sept. 29, 1882.	
	E. on a random line bet. Secs. 5 & 8.	
	Ascend. Var. 21°E.	