

South Bdy., T.2 N., R. 27 E., W. M.
 As surveyed by Ebenezer E. Haft, U.S. Deputy Surveyor,
 Under Contract No. 91,
 Dated Sept. 11, 1860.

Chains		Feet
	<p>From the Cor. to Tps. 1 & 2 N., Rs. 26 & 27 E., I run E. on random line bet. said Tps. Set temp. $\frac{1}{2}$ and mile posts at 40.00 & 80.00 chs.</p> <p>I find the Tp. line to be 6 miles, 6 chs. & 20 lks. and the falling to be 811 lks. N. of the Tp. Cor.</p> <p>Hence the correction for the true line will be, 6 chs. & 20 lks. E. & $131\frac{1}{3}$ lks. S. per mile.</p> <p>From the Cor. to Tps. 1 & 2 N., Rs. 27 & 28 E., I run N. $89^{\circ}54'W.$ on true line bet. Secs. 1 & 36. Var. $20^{\circ} E.$</p>	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 1, 2, 35 & 36, in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
	Soil; 3rd & 2nd rate.	
	Land; high & rolling.	
	<p>N. $89^{\circ}54'W.$ bet. Secs. 2 & 35. Var. $19^{\circ}45'E.$</p>	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits, & deposited 1 pt. charcoal, as per instructions.	
60.00	Leave table land, 150 ft. high and descend.	
80.00	Set post for Cor. to Secs. 2, 3, 34 & 35, in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
	Soil; 2nd & 3rd rate.	
	<p>N. $89^{\circ}54'W.$ bet. Secs. 3 & 34. Var. $19^{\circ}40'E.$</p>	
15.00	Foot of descent & enter Butter Creek bottom.	
38.15	Butter Creek, 20 lks. wide, runs N. $20^{\circ}W.$ Willow undergrowth on creek, 50 lks. wide.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
44.00	Leave Butter Creek bottom & ascend table land.	
80.00	Set post for Cor. to Secs. 3, 4, 33 & 34, in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	