

S. Bdy., T. 2 N., R. 27 E., W. M.

Chains		Feet
	Soil; on Butter Creek bottom, 1st rate- remainder, 2nd & 3rd rate.	
	Subdivisional Lines, T.2 N., R.27 E., W. M. As surveyed by Same Surveyor, Under Same Contract & date.	
	From the Cor. to Secs. 1, 2, 35 & 36 on S. Bdy. of Tp., I run	
	N. bet. Secs. 35 & 36. Descend gradually.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
80.00	Set post, for Cor. to Secs. 25, 26, 35 & 36, in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
	Soil; 3rd rate, producing grass.	
	Land; gradually descending to the N.	
	E. on random line bet. Secs. 25 & 36.	
	Var. 20° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.65	Intersect E. Bdy., 28 lks. S. of Cor. to Secs. 25, 26, 35 & 36, from which Cor., I run	
	S. 89° 48' W. on true line bet. Secs. 25 & 36.	
39.82 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
79.65	The Cor. to Secs. 25, 36, 26 & 35.	
	Soil; 2nd & 3rd rate, producing grass.	
	Land; high & rolling.	
	N. bet. Secs. 25 & 26.	
	Var.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 23, 24, 25 & 26, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
	The soil of light porous nature, producing abundance of bunch grass.	
	Land; high & rolling.	