

Subdivisional Lines, T.2 N., R.27 E., W. M.

Chains		Feet
	<p>E. on random line bet. Secs. 24 & 25. Var. 19°55'E.</p>	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.45	<p>Intersect E. Bdy. of Tp., 40 lks. S. of Cor. to Secs. 24, 25, 19 & 30, from which Cor., I run, S.89°43'W. on true line bet. Secs. 24 & 25.</p>	
39.72 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
79.45	<p>The Cor. to Secs. 23, 24, 25 & 26. Soil; 2nd & 3rd rate, producing grass. Land; high & rolling.</p>	
	N. bet. Secs. 23 & 24.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	<p>Set post for Cor. to Secs. 13, 14, 23 & 24, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Soil; 3rd rate, producing grass. Land; high & rolling.</p>	
	<p>E. on random line bet. Secs. 13 & 24. Var. 19°45'E.</p>	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.80	<p>Intersected E. Bdy. of Tp., 65 lks. S. of Cor. to Secs. 13, 14, 18 & 19, from which Cor., I run S.89°32'W. on true line bet. Secs. 13 & 24.</p>	
39.90	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits, deposited 1 pt. charcoal, as per instructions.	
79.80	<p>The Cor. to Secs. 13, 14, 23 & 24, in mound, with trench, pits & deposited 1 pt. charcoal, as per instructions. Soil; 2nd & 3rd rate, producing grass. Land; high & rolling to the N.</p>	
	N. bet. Secs. 13 & 14.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	