

## Subdivisional Lines, T. 2 N., R. 27 E., W. M.

Chains		Feet
40.20	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.40	The Cor. to Secs. 26, 27, 34 & 35. Soil; 2nd & 3rd rate, producing grass. Land; gently rolling.	
N. bet. Secs. 26 & 27.		
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 22, 23, 26 & 27, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Soil; 2nd & 3rd rate, producing grass. Land; rolling.	
E. on random line bet. Secs. 23 & 26.		
Var. 19° 45' E.		
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.79	Intersect N. & S. line, 5 lks. N. of Cor. to Secs. 23, 24, 25 & 26, from which Cor., I run, N. 89° 58' W. on true line, bet. Secs. 23 & 26.	
39.89 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
79.79	The Cor. to Secs. 22, 23, 26 & 27. Soil; 2nd & 3rd rate, producing grass. Land; gently rolling.	
N. bet. Secs. 22 & 23.		
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
71.10	Butter Creek, 20 lks. wide, runs N., N.E.	
80.00	Set post for Cor. to Secs. 14, 15, 22 & 23, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Land; S. part rolling 3rd rate, N. part level 1st rate.	