

## Subdivisional Lines, T.2 N., R.27 E., W. M.

Chains		Feet
	E. on random line bet. Secs. 14 & 23. Var. 19°45'E.	
40.40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.60	Intersect N. & S. line, 25 lks. S. of Cor. to Secs. 13, 14, 23 & 24, from which Cor., I run S.89° 49' W. on true line bet. Secs. 14 & 23.	
39.80	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
74.60	Enter Butter Creek bottom & leave rolling ground.	
77.05	Butter Creek, 25 lks. wide, runs N. & N.E.	
79.60	The Cor. to Secs. 14, 15, 22 & 23. Land; on Butter Creek bottom, level & 1st rate- remainder, rolling, 2nd & 3rd rate.	
	N. bet. Secs. 14 & 15.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 10, 11, 14 & 15, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Land; level & Soil 1st rate & 2nd rate. Some sage wood.	
	E. on random line bet. Secs. 11 & 14. Var. 19°50'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.53	Intersect N. & S. line, 2 lks. S. of Cor. to Secs. 11, 12, 13 & 14, from which Cor., I run, S.89°59' W. on true line bet. Secs. 11 & 14.	
24.50	Enter Butter Creek bottom, course N.E.	
39.00	Enter Butter Creek, which is dry at this place.	
39.75	Set post for $\frac{1}{4}$ Sec. Cor., in Butter Creek channel, from which, A balm, 12 ins. diam., brs. N.40°E., 12 lks. dist. A haw tree, 4 ins. diam., brs. S.28°W., 26 lks. dist.	
40.00	Leave Butter Creek.	
79.53	The Cor. to Secs. 10, 11, 14 & 15.	