

Subdivisional Lines, T.2 N., R.27 E., W. M.

Chains		Feet
	Soil on Butter Creek bottom, 1st rate. Remainder, rolling, producing grass with some sage wood.	
	N. bet. Secs. 10 & 11.	
39.00	Trail up Butter Creek, course S.W.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
	Leave Butter Creek bottom & ascend hill.	
55.00	Top of hill, 100 ft. high, brs. N.E. & S.W.	
80.00	Set post for Cor. to Secs. 10, 11, 2 & 3, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
	Soil on Butter Creek bottom, 1st rate & level- on N. part of line, 2nd rate & hilly.	
	E. on random line bet. Secs. 2 & 11.	
	Var. 19°55'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
79.80	Intersect N. & S. line, 7 lks. N. of Cor. to Secs. 12, 11, 1 & 2, from which Cor., I run	
	N.89°57'W. on true line bet. Secs. 2 & 11.	
39.90	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
50.70	Road up Butter Creek, S., S.W. Ascend hill.	
79.80	The Cor. to Secs. 10, 11, 2 & 3.	
	Land on Butter Creek, level & 1st rate. Remainder, hilly and 3rd rate.	
	N. on random line bet. Secs. 2 & 3.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.54	Intersect N. Bdy. of Tp., 10 lks. W. of Cor. to Secs. 2, 3, 34 & 35, from which Cor., I run	
	S.0°4'W. on true line bet. Secs. 2 & 3.	
4.50	The main road from the Dalles to Walla Walla, course N.E.	
40.54	Set post for $\frac{1}{4}$ Sec. Cor., in mound, and deposited 1 pt. charcoal & made trench & pits, as per instructions.	