

Subdivisional Lines, T.2 N., R.27 E., W. M.

Chains		Feet
	E. on random line bet. Secs. 15 & 22. Var. 19°E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.20	Intersect N. & S. line, 22 lks. S. of Cor. to Secs. 15, 14, 22 & 23, from which Cor., I run, S. 89°51' W. on true line bet. Secs. 15 & 22.	
40.10	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; de- posited 1 pt. charcoal, as per instructions.	
59.00	Trail up Butter Creek, brs. S.W. Enter high land & leave bottom.	
80.20	The Cor. to Secs. 15, 16, 21 & 22. Soil; principally 2nd & 3rd rate, on the bottom, level with some sage.	
<hr/>		
	N. bet. Secs. 15 & 16.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 9, 10, 15 & 16, in mound, with trench & pits & deposited 1 pt. charcoal, as per instruc- tions. Land; rolling. Soil; 3rd rate.	
<hr/>		
	E. on random line bet. Secs. 10 & 15. Var. 19°20'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.21	Intersect N. & S. line, 5 lks. S. of Cor. to Secs. 10, 11, 14 & 15, from which Cor., I run S. 89°58' W. on true line bet. Secs. 10 & 15.	
17.00	Trail up Butter Creek, brs. S.W.	
40.10 $\frac{1}{2}$	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions. Leave bottom and enter hills.	
80.21	The Cor. to Secs. 10, 9, 16 & 15. Soil; 1st & 2nd rate. The bottom is principally covered with sage wood.	