

## Subdivisions of T. 2 N., R. 28 E.

Chains	
	North between secs. 9 and 10.
	Var. 19° 45' East.
	Descend hill.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. to 3, 4, 9, and 10 in mound of Earth &c as per instructions. Foot of hill.
	Land, hilly.
	Soil, 2nd rate.
	East on random line between secs. 3 and 10.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
80.00	Intersect N. and S. line, 20 links North of sec. corner. N. 89° 51' W., on true line, between secs. 3 and 10.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions. Spring bears S. 40° W. 25 chs. dist.
80.00	The corner to secs. 3, 4, 9 and 10.
	Land, level.
	Soil, 1st rate.
	North on random line between secs. 3 and 4.
	Var. 20° 30' East.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
80.30	Intersect North boundary at the corner to secs. 3 and 4. South, on true line, between secs. 3 and 4.
40.30	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.30	The corner to secs. 3, 4, 9 and 10.
	Land, level.
	Soil, 1st rate.
	October 7, 1859.
	North between secs. 32 and 33.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 28, 29, 32 and 33 in mound of Earth &c as per instructions.