

Subdivisions of T. 2 N., R. 28 E.

Chains	
	instructions.
80.00	Set post for corner to secs. 16, 17, 20 and 21 in mound of Earth &c as per instructions. Land, level. Soil, 1st rate.
40.00	East on random line between secs. 16 and 21. Set post for temp. $\frac{1}{4}$ sec. corner.
80.06	Intersect N. and S. line, 78 links North of corner. N. $89^{\circ} 27' W.$, on true line, between secs. 16 and 21. Descend hill.
40.03	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.06	Foot of hill. The corner to secs. 16, 17, 20 and 21. Land, hilly. Soil, 2nd rate.
40.00	North between secs. 16 and 17. Var. 20° East. Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 8, 9, 16 and 17, in mound of Earth &c as per instructions. Land, gently rolling. Soil, 1st rate.
40.00	East on random line between secs. 9 and 16. Var. 20° East. Set temp. $\frac{1}{4}$ sec. corner.
80.60	Intersect N. and S. line, 70 links North of sec. corner. N. $89^{\circ} 30' W.$, on true line, between secs. 9 and 16.
15.00	Descend hill.
40.30	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.60	The corner to secs. 8, 9, 16 and 17. Foot of hill. Land, hilly.