

Exterior and subdivisions of T. 2 N., R. 29 E.
 Surveyed by David P. Thompson under contract No. 83.
 Dated July 22, 1859.

Chains	<p>From the established corner to Townships 1 and 2, North of Ranges 28 and 29 East. I run.</p> <p>North between secs. 31 and 36.</p> <p style="text-align: center;">Var. 20° East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.</p> <p>80.00 Set post for corner to secs. 30, 31 25 and 36 in mound of Earth &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good, 2nd rate.</p>
	<p>North between secs. 25 and 30.</p> <p style="text-align: center;">Var. 19° 30' East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of Earth.</p> <p>80.00 Set post for corner to secs. 24, 25, 19 and 30 in mound of Earth &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good, 2 nd rate.</p>
	<p>North between sec. 19 and 24.</p> <p style="text-align: center;">Var. 19° 45' East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.</p> <p>80.00 Set post for corner to secs. 18, 19 13 and 24 in mound of Earth &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good, 2nd rate.</p>
	<p>North between secs. 13 and 18.</p> <p style="text-align: center;">Var. 19° 45' East.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.</p> <p>74.50 Indian Trail bears N.W . and S.E.</p> <p>80.00 Set post for corner to secs. 12, 13 7 and 18 in mound of Earth &c as per instructions.</p> <p>Land, good, 2nd rate, rolling</p>