

T. 2 N., R. 29 E.

Chains	<p>North between secs. 7 and 12.</p> <p style="text-align: right;">Var. 20° 30' East.</p> <p>3.50 Ravine and Trail bears S.W. and N.E.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.</p> <p>80.00 Set post for corner to secs. 6, 7, 1 and 12 in mound of Earth &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good, 2nd rate.</p>
	<p>North between secs. 1 and 6.</p> <p style="text-align: right;">Var. 19° 15' East.</p> <p>7.40 Indian Trail bears N.E. and S.W.</p> <p>40.00 Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.</p> <p>80.00 Set post for corner to Townships 2 and 3, North of Ranges 28 and 29 East, in mound of Earth &c as per instructions.</p> <p style="text-align: right;">Var. 20$\frac{1}{2}$° East.</p> <p>Land, gently rolling.</p> <p>Soil, good, 2nd rate.</p> <p style="text-align: right;">August 24, 1859.</p>
	<p>From the corner to Townships 2 and 3, North of Ranges 28 and 29 East, I run a random line between said Townships setting temporary half mile and mile post at 40.00 and 80.00 chains.</p> <p>I find the Township line to be 6 miles, 8 chains and 70 links, and the falling to be 400 links South of corner. The correction will, therefore, be 8.70 links West and 66 $\frac{2}{3}$ links North per mile.</p>
	<p>From the established corner to Townships 2 and 3, North of Ranges 29 and 30 East. I run.</p> <p>S. 89° 32' W., on true line, between secs. 1 and 36.</p> <p style="text-align: right;">Var. 19° 30' East.</p> <p>28.00 Leave bottom, bears N.W. and S.E.</p>