

## Subdivisions of T. 2 N., R. 29 E.

Chains	Land, hilly. Soil, 2nd rate.
	East, on random line, between secs. 25 and 36.
40.00	Set temp. $\frac{1}{4}$ sec. post.
79.94	Intersect East boundary 20 links North of corner to secs. 25 and 36.
	North $89^{\circ} 52'$ W., on true line, between secs. 25 and 36.
39.97	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
79.94	The corner to secs. 25, 26, 35 and 36. Land, gently rolling. Soil, 2nd rate.
	North between secs. 25 and 26. Var. $20^{\circ} 10'$ East.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 23, 24, 25 and 26 in mound of Earth &c as per instructions. Land, gently rolling. Soil, good, 2nd rate.
	East on random line between secs. 24 and 25.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
79.83	Intersect East boundary, 18 links North of sec. corner. N. $89^{\circ} 52'$ W., on true line, between secs. 24 and 25.
39.92	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
79.83	The corner to secs. 23, 24, 25 and 26. Land, gently rolling. Soil, good, 2nd rate.
	North between secs. 23 and 24. Var. $20^{\circ} 10'$ East.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of stone.