

Subdivisions of T. 2 N., R. 29 E.

Chains	East on random between secs. 26 and 35.
40.00	Set post for temp. $\frac{1}{4}$ sec. corner.
79.50	Intersect N. and S. line, 70 links South of sec. corner. S. $89^{\circ} 30'$ W., on true line, between secs. 26 and 35 .
39.75	Set post for $\frac{1}{4}$ sec. corner in mound of stone.
59.01	Indian Trail to Butter Creek bears N.W. and S.E.
63.00	Dry creek in Ravine bears N.W. and S.E.
79.50	The corner to secs. 26, 27, 34 and 35. Land, hilly. Soil, 2nd rate.
	North between secs. 26 and 27. Var. 19° East.
20.00	Dry creek in Ravine bears N.W. and S.E.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 22, 23, 26 and 27. Land, gently rolling. Soil, good, 2nd rate.
	East, on random line, between secs. 23 and 26.
40.00	Set temp. $\frac{1}{4}$ sec. corner.
79.85	Intersect N. and S., 70 links South of sec. corner. S. $89^{\circ} 30'$ W., on true line, between secs. 23 and 26.
39.92	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
79.85	The corner to secs. 22, 23, 26 and 27. Land, gently rolling. Soil, 2nd rate.
	North between secs. 22 and 23. Var. 20° East.
.50	Indian Trail from Umatilla River to Butter Creek.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per Instructions.
80.00	Set post for corner to secs. 22, 23, 14 and 15 in mound