

Subdivisions of T.2 N., R. 29 E.

Chains	
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.
87.35	Intersect West boundary, 12 links North of sec. corner. N. $89^{\circ} 55'$ E., on true line, between secs. 18 and 19.
47.35	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
87.35	The corner to secs. 17, 18, 19 and 20. Land, gently rolling. Soil, 2nd rate.
	North between secs. 17 and 18. Var. $20^{\circ} 15'$ East.
40.00	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.00	Set post for corner to secs. 7, 8, 17 and 18, in mound of Earth with pits trench &c as per instructions. Land, gently rolling. Soil, good, 2nd rate.
	East, on random line, between secs. 8 and 17.
40.00	Set post for temporary $\frac{1}{4}$ sec. corner.
80.04	Intersect N. and S. line, 70 links North of sec. corner. S. $89^{\circ} 30'$ W., on true line, between secs. 8 and 17.
40.02	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
80.04	The corner to secs. 7, 8, 17 and 18. Land, gently rolling. Soil, 1st rate.
	West, on random line between secs. 7 and 18.
40.00	Set temp. $\frac{1}{4}$ sec. corner.
87.90	Intersect West boundary at sec. corner. East, on true line, between secs. 7 and 18.
26.46	Indian Trail bears S.W. and N.E.
47.90	Set post for $\frac{1}{4}$ sec. corner in mound of Earth &c as per instructions.
87.90	The corner to secs. 7, 8, 17 and 18.