

Exterior boundaries T. 2 N.R. 30 E.

Chains	North between Secs. 1 & 6. Variation 19° East.
37.00	Ravine bears N.E. & S.W.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
74.00	Enter bottom, course bears E & W.
80.00	Set post for corner to Tps. 2 & 3 North of Ranges 29 & 30, East in mound of earth with pits, trench &c., as per instructions.
	Land, rolling. Soil, good 2nd rate.
<hr/> <p>From the corner to Townships 2 & 3, North of Ranges 29 & 30 East, I run a random line between said townships, setting half mile and mile posts at 40.00 and 80.00 chains. I find the length of the line to be 6 miles, 6 chains and 20 links, and the falling to be 80 links South of Township corner.</p> <hr/> <p>North boundary T 2. N. R. 30 E.</p> <hr/>	
	S. 89° 54' W. on true line between Secs. 1 & 36.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 1, 2, 35 & 36 in mound of earth &c., as per instructions.
	Land, hilly. Soil, 2nd rate.
<hr/> <p>S. 89° 54' W. on true line between Secs. 2 & 35. Variation 20° East.</p>	
40.00	Set post for 1/4 Sec. corner in mound of earth with pits, trench &c., as per instructions.
80.00	Set post for corner to Secs. 2, 3, 34 & 35 in mound of earth &c., as per instructions.
	Land, hilly. Soil, 2nd rate.