

Subdivisions of T.2 N.R. 30 E.

Chains	East on a random line between Secs. 13 & 24.
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
80.25	Intersect East boundary 61 links South of Sec. corner. S. 89° 34' W. on true line between Secs. 13 & 24.
40.13	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.25	The corner to Secs. 13, 14, 23 & 24. Land, gently rolling. Soil, 1st rate.
	August 27th, 1859.
	North between Secs. 13 & 14. Variation 20° East.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 11, 12, 13 & 14 in mound of earth &c., as per instructions. Land, rolling. Soil, 2nd rate.
	East on a random line between Secs. 12 & 13.
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
80.60	Intersect East boundary 49 links South of Sec. corner. S. 89° 39' W. on true line between Secs. 12 & 13.
40.30	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
80.60	The corner to Secs. 11, 12, 13 & 14. Land, rolling. Soil, 2nd rate.
	North between Secs. 11 & 12. Variation 20° East.
	Descend hill.
20.50	Foot of hill. Enter bottom, bears E. & W.