

## Subdivisions T. 2 N. R. 30 E.

Chains	
	Land, gently rolling. Soil, 2nd rate.
	East on random line between Secs. 9 & 16.
40.00	Set post for temp. 1/4 Sec. corner.
80.50	Intersect N & S line at Sec. corner.
	West on true line between Secs. 9 & 16.
40.25	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.50	The corner to Secs. 8, 9, 16 & 17.
	Land, gently rolling. Soil, 2nd rate.
	North between Secs. 8 & 9.
	Variation 21° 00' East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
45.00	Descend hill, bears E. & W.
57.50	Enter timbered bottom, bears E. & W.
62.00	To slough, 40 links wide, bears W.
11.00	Umatilla River 130 links wide, runs West.
80.00	Set post for corner to Secs. 4, 5, 8 & 9, from which a balm 8 in. diam. bears N. 7° E. 19 links dist. a " 10 " " " N. 83° W. 20 " " a " 5 " " " S. 24° W. 26 " " a birch 6 " " " S. 20° E. 13 " "
	Land, 2nd rate. Soil, 1st & 2nd rate. Timber on Bottom, balm.
	East on a random line between Secs. 4 & 9.
40.00	Set post for temp. 1/4 Sec. corner.
80.50	Intersect N & S line 7 links North of Sec. corner. N. 89° 57' W. on true line between Secs. 4 & 9.
40.25	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.