

Subdivisions T. 2 N. R. 30 E.

Chains	
77.50	Enter bottom, course bears S. 75° E.
80.50	The corner to Secs. 4, 5, 8 & 9. Land, broken. Soil, 3rd rate, stony.
<hr/>	
	North on random line between Secs. 4 & 5. Variation 20° East.
40.00	Set post for temp. 1/4 Sec. corner.
80.13	Intersect North boundary 12 links West of Sec. corner. So. 0° 05' W. on true line between Secs. 4 & 5.
40.13	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.13	The corner to Secs. 4, 5, 8 & 9. Land, broken. Soil, 2nd & 3rd rate. Stony. Sept. 1, 1859.
<hr/>	
	North between Secs. 31 & 32.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 29, 30, 31 & 32 in mound of earth &c., as per instructions. Land, rolling. Soil, 2nd rate.
<hr/>	
	East on random line between Secs. 29 & 32.
40.00	Set post for temp. 1/4 Sec. corner.
80.06	Intersect N & S line at Sec. corner West on true line between Secs. 29 & 32.
40.03	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.06	The corner to Secs. 29, 30, 31 & 32. Land, rolling. Soil, 2nd rate.