

## E. Bdry., T. 2 N., R. 31 E.

Chains	
80.00	<p>Set post for corner to Secs. 19, 30, 24 &amp; 25, drove a charred stake and raised mound with trench, as per instructions.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p>
<hr/> <p>North on East boundary of Sec. 24</p>	
<p style="text-align: right;">Variation 21°00' East</p>	
40.00	<p>Set post for <math>\frac{1}{4}</math> Sec. corner, drove charred stake and raised mound with trench, as per instructions.</p>
57.00	<p>Entered Mr. Whitney's field, course N.W. &amp; S.E.</p>
58.00	<p>Foot of hill, and enter Birch Creek bottom, course N.E. &amp; S.W.</p>
63.00	<p>To Birch Creek, 40 links wide (now dry), course North.</p>
79.00	<p>Leave Birch Creek, course N. 25° W.</p>
80.00	<p>Set a post for corner to Secs. 13, 24, 18 &amp; 19, from which</p> <p style="padding-left: 40px;">a willow 5 in. dia. bears N. 52 West, 51 links dist.</p> <p>No other bearing trees convenient, drove charred stake and raised mound with trench, as per instructions.</p> <p>Land, North half, level creek bottom; soil, 1st rate;</p> <p>South half, rolling grass hills; soil 2nd rate.</p>
<hr/> <p>North on East boundary of Sec. 13.</p>	
<p style="text-align: right;">Variation 19°30' E.</p>	
1.00	<p>To Birch Creek, course N.E.</p>
2.75	<p>" " " " N. W.</p>
16.25	<p>Leave Whitney's field at N.E. Corner, course N.68° W. and S. 27° E.</p>
16.40	<p>Mr. Whitney's house bears N. 80° W.</p>
17.00	<p>Leave valley and ascend hill, course S.20° E. &amp; N.W.</p>
40.00	<p>Set a post for <math>\frac{1}{4}</math> Sec. cor., drove charred stake and raised mound, as per instructions.</p>
44.75	<p>Mr. Whitney's house bears S.22° W.</p>
67.50	<p>Foot of hill and enter Umatilla River bottom. Course E&amp;W.</p>