

N. Edry. T. 2 N., R. 31 E.

Chains	
	<p>S. 89° 17' E. on true line along the North boundary of Sec. 1.</p> <p style="text-align: right;">Variation 19° 45' East.</p>
35.25	A wagon road from Dalles to Walla Walla, course N.E. & S.75°W.
40.00	Set a post for cor. to $\frac{1}{4}$ Sec. Drove charred stake and raised mound with trench, as per instructions.
80.00	The corner to Townships 2 & 3 North, Ranges 31 & 32 East. Land, level prairie. Soil, 2nd rate.
	Oct. 20th, 1860.
	<hr/> <p>General Description</p>
	<p>This Township contains a large amount of first rate land for farming.</p> <p>The Umatilla River bottoms are well timbered with balm and birch. Umatilla River runs through, near the center of the Township. Its bottoms are rich soil and good for farming purposes.</p> <p>The Township will admit of a large settlement and should, therefore, be subdivided.</p>
	<hr/> <p>Field Notes of the Subdivision Lines in T. 2 N., R. 31 East.</p>
	<p>Subdivisions commenced October 20th, 1860.</p> <p>From the corner to Secs. 1, 2, 35 & 36 on the South boundary of the Township, I run,</p> <p>North between Secs. 35 and 36.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
80.00	Set a post for corner to Secs. 25, 26, 35 & 36, drove charred stake and raised mound with trench, as per instructions.
	Land, broken and stony.