

Subdivisions, T. 2 N., R. 31 E.

Chains	
	<p>East on a random line between Secs. 26 &amp; 35.</p> <p style="text-align: right;">Variation 20° 15' E.</p>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.69	Intersected N & S line 68 links North of the corner to Secs. 25, 26, 35 and 36, from which corner I run N. 89° 30' W. on a true line between Secs. 26 & 35.
39.34	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
79.69	The corner to Secs. 26, 27, 34 and 35. Land, rolling grass hills. Soil, 2nd rate.
<hr/>	
	North between Secs. 26 and 27.
18.90	To a dry ravine, course N.E.
40.00	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
42.50	To a dry ravine, course East.
80.00	Set a post for corner to Secs. 22, 23, 26 and 27. Drove charred stake and raised mound with trench, as per instructions. Land, broken. Soil, 2nd and 3rd rate.
<hr/>	
	East on a random line between Secs. 23 and 26.
	Variation 20° 00' E.
40.00	Set a temporary $\frac{1}{4}$ Sec. corner.
79.75	Intersected N & S line, 62 links North of the corner to Secs. 23, 24, 25 and 26, from which corner I run N. 89° 34' W. on a true line between Secs. 23 and 26.
20.00	To a dry ravine, course N.E.
39.87	Set a post for $\frac{1}{4}$ Sec. corner. Drove stake and raised stone mound, as per instructions.
79.75	The corner to Secs. 22, 23, 26 & 27. Land, rolling. Soil, 2nd rate.