

Subdivisions T.2 N., R. 31 E.

Chains	
80.00	Set post for corner to Secs. 15, 16, 21 and 22, drove charred stake and raised mound with trench, as per instructions. Land, broken hills and stony.
<hr/>	
East on random line between Secs. 15 and 22.	
Variation 19° 45' E.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.23	Intersect N & S line, 13 links North of the corner to Secs. 14, 15, 22 and 23, from which corner I run N.89° 55' W. on a true line between Secs. 15 and 22.
40.11	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
78.23	To a deep, stony ravine, course North.
80.23	The corner to Secs. 15, 16, 21 and 22. Land, broken. Soil, 2nd and 3rd rate.
<hr/>	
North between Secs. 15 and 16.	
19.00	Foot of hill and enter Umatilla River bottom, bearing E & W.
40.00	Set a post for $\frac{1}{4}$ Sec. corner, from which A Balm Gilliad, 19 in. diam. bears S.4°30' W., 105 links distant; A Balm Gilliad, 12 in. diam. bears N.19° E. 306 links distant.
48.00	Left bank of Umatilla River, 100 links wide, runs West.
49.00	Foot of hill, bearing E & W.
80.00	Set a post for corner to Secs. 9, 10, 15 and 16, drove stake and raised mound with trench, as per instructions. Land, sandy soil. Balm Gilliad timber on the river.
<hr/>	