

Subdivisions, T. 2 N., R. 31 E.

Chains	
	<p>East on random line between Secs. 10 & 15.</p> <p style="text-align: right;">Variation 23°30' E.</p>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.50	<p>Intersected N & S line, 13 links North of the corner to</p> <p>Secs. 10, 11, 14 and 15, from which corner I run</p> <p>N. 89° 54' W. on a true line between Secs. 10 & 15.</p>
38.50	To a dry ravine, course South.
40.25	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
80.50	<p>The corner to Secs. 9, 10, 15 & 16.</p> <p>Land, rolling.</p> <p>Soil, 2nd and 3rd rate.</p>
<hr/>	
	<p>North between Secs. 9 & 10.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner and raised stone mound, as per instructions.
80.00	<p>Set post for corner to Secs. 3, 4, 9 and 10, drove charred stake and raised mound with trench, as per instructions.</p> <p>Land, broken grass hills.</p> <p>Soil, 2d & 3rd rate.</p>
<hr/>	
	<p>East on random line between Secs. 3 and 10.</p> <p style="text-align: right;">Variation 20°00' East</p>
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.50	<p>Intersected N & S line 13 links North of the corner to</p> <p>Secs. 2, 3, 10 & 11, from which I run</p> <p>N. 89° 52' W. on a true line between Secs. 3 and 10.</p>
40.25	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
80.50	<p>The corner to Secs. 3, 4, 9 & 10.</p> <p>Land, rolling prairie upland.</p> <p>Soil, 2nd rate.</p>