

Subdivisions, T.2 N., R. 31 E.

Chains

stake and raised mound with trench, as per instructions.
Land, broken and stony.

East on a random line between Secs. 21 & 28.

Variation 18°15' East

40.00 Set temporary $\frac{1}{4}$ Sec. corner.

80.20 Intersect N & S line 70 links North of the corner to
Secs. 21, 22, 27 & 28, from which I run

N. 89°30' W. on a true line between Secs. 21 and 28.

40.10 Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and
raised mound with trench, as per instructions.

57.00 To a deep, dry ravine, course North.

79.20 To a deep, dry ravine, course N.E.

80.20 The corner to Secs. 20, 21, 28 & 29.

Land, rolling.

Soil, 2nd rate.

North between Secs. 20 & 21.

40.00 Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and rais-
ed mound with trench, as per instructions.

41.50 To a deep, rocky ravine, course N.E.

80.00 Set a post for corner to Secs. 16, 17, 20 and 21. Drove
charred stake and raised mound with trench, as per
instructions.

Land, broken.

Soil, 2nd rate.

East on a random line between Secs. 16 & 21.

Variation 19° 45' East

40.00 Set temporary $\frac{1}{4}$ Sec. corner.

80.50 Intersected N & S line 40 links North of the corner to
Secs. 15, 16, 21 & 22, from which corner I run

N. 89° 43' West on a true line between Secs. 16 & 21.

40.25 Set post for $\frac{1}{4}$ Sec. corner and raised stone mound, as
per instructions.