

## Subdivisions, T. 2 N., R. 31 E.

Chains	
46.50	To a deep, rocky ravine, course North.
80.50	The corner to Secs. 16, 17, 20 and 21. Land, broken, 2nd rate; some stone.
North between Secs. 16 & 17.	
24.00	Foot of steep hill and enter River bottom, course E & W.
31.50	To the left bank of the Umatilla River, 125 links wide, course West.
40.00	Set a post for $\frac{1}{4}$ Sec. corner, drove charred stake and raised mound with trench, as per instructions.
46.00	Leave river bottom and begin to ascend hill, bearing E&W.
80.00	Set a post for corner to Secs. 8, 9, 16 & 17. Drove charred stake and raised mound with trench, as per instructions.
Land, 1st, 2nd and 3rd rate, soil.	
Timber on river, Balm Gilliad.	
East on a random line between Secs. 9 and 16.	
Variation, 17°30' E.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.40	Intersected N & S line 35 links North of the corner to Secs. 9, 10, 15 & 16, from which corner I run, N. 89°45' W. on a true line between Secs. 9 & 16.
12.50	To a deep, dry ravine, course South.
40.20	Set post for $\frac{1}{4}$ Sec. corner and raised stone mound, as per instructions.
57.25	To a deep, stony ravine(dry), course South.
80.40	The corner to Secs. 8, 9, 16 and 17. Land, broken grass hills.
North between Secs. 8 & 9.	
40.00	Set post for $\frac{1}{4}$ Sec. corner and raised stone mound, as per instructions.
80.00	Set a post for corner to Secs. 4, 5, 8 and 9, drove charred stake and raised mound of stone.