

Subdivisions, T.2 N., R. 31 E.

Chains	
	Land, rolling. Soil, 2nd rate.
	East on random line between Secs. 29 & 32. Variation 20°00' East
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.50	Intersected N & S line 72 links North of the corner to Secs. 28, 29, 32 & 33, from which corner I run, N. 89° 29' W. on a true line between Secs. 29 & 32.
38.00	To dry ravine, course N.
39.75	Set post for corner to $\frac{1}{4}$ Sec. Drove charred stake and raised mound with trench, as per instructions.
79.50	The corner to Secs. 29, 30, 31 & 32. Land, broken, 3rd rate grass land.
	West on random line between Secs. 30 & 31. Set temporary $\frac{1}{4}$ Sec. corner.
89.36	Intersected West boundary of Township 98 links South of the corner to Secs. 30 & 31, from which corner I run, S. 89° 18' E. on a true line between Secs. 30 & 31.
89.36	Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and rais- ed mound with trench, as per instructions.
89.36	The corner to Secs. 29, 30, 31 & 32. Land, rolling grass hills. Soil, 2nd rate.
	North between Secs. 29 & 30. Set post for $\frac{1}{4}$ Sec. corner, drove charred stake and rais- ed mound with trench, as per instructions.
40.00	
50.00	Enter broken hills.
80.00	Set post for corner to Secs. 19, 20, 29 and 30, and rais- ed stone mound, as per instructions.
	East on random line between Secs. 20 & 29. Variation 19°00' East.