

Exteriors, T.2 N., R. 32 E.

Chains

80.00 Set post 12, 13, 7 & 18 in mound of earth, with charred stake, pits, trench &c., as per instructions.

Land, rolling.

Soil, good 2nd rate.

North on East boundary of Sec. 12.

Variation 19°30' East

7.70 Road bears E & W.

40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth, with charred stake, pits, trench &c., as per instructions.

47.00 Road bears E & W.

55.00 Enter timber, bears E & W.

61.30 Umatilla River 80 links wide runs West.

80.00 Set post for corner to Secs. 6, 7, 1 & 12, from which

an alder 5 in. diam. bears N.53°E., 87 links dist.

a cherry 5 " " " S.40° E.44' links dist.

a willow 5 " " " N.35° W., 46 " "

" " 5 " " " S.75° W., 63 " "

Land, level.

Soil, 1st rate.

Timber, Cottonwood, Birch and Willow.

September 10th, 1864.

North on East boundary of Sec. 1.

Variation 20° East.

3.00 Leave timber, bears E & W.

40.00 Set stone 15 x 10 x 4 in. for $\frac{1}{4}$ Sec. corner.

64.75 Dry bed of creek, course S.W. Ascend hill.

80.00 Set post for corner to Townships 2 & 3 North Range No.32 and 33 East, in mound of earth with charred stake, pits, trench &c., as per instructions.

I run West between said Townships, setting temporary half mile and mile posts at 40.00 and 80.00 chains.

I find the Township line to be 6 miles, 6 chains & 50 lks.