

Chains

River, which flows through the North part of the Township from East to West.

There are a large number of settlers in this Township.

The County Seat of Umatilla County is in it and it should be subdivided.

Field Notes of the Survey of the Subdivisions of T. 2 N., R. 32 E. Survey by Daniel Chaplin, under Contract No.107, dated Sept.21,1864.

North between Secs. 35 & 36.

12.60 Road bears E & W.
 40.00 Set stone 16 x 8 x 5 for $\frac{1}{4}$ Sec. corner.
 60.00 Ravine bears N. W.
 80.00 Set stone 20 x 12 x 5 for corner to Secs. 35, 36, 25 & 26.
 Land, rolling.
 Soil, 2nd rate.

East on a random line between Secs. 25 & 36.

40.00 Set post for temporary $\frac{1}{4}$ section corner.
 79.59 Intersect East boundary 35 links South of corner to Secs. 25 & 36, from which I run S. 89° 45' W. on a true line between Secs. 25 & 36.
 39.79 Set post for $\frac{1}{4}$ Sec. corner in mound of earth, with charred stake, pits &c., as per instructions.
 79.59 The corner to Secs. 25, 26, 35 & 36.
 Land, gently rolling.
 Soil, good 2nd rate.

North between Secs. 25 & 26.

Variation 21° East

40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.
 80.00 Set post for corner to Secs. 23, 24, 25 & 26 in mound of earth with charred stake, pits &c., as per instructions.