

9
Subdivisions, T. 2 N., R. 32 E.

Chains	
80.00	Set post for corner to Secs. 26, 27, 34 & 35 in mound of earth, with charred stake, pits &c., as per instructions. Land, rolling. Soil, 2nd rate.
<hr/>	
	East on a random line between Secs. 26 & 35.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersect N. W. line at cor. to sections 25, 26, 25 & 36, from which corner I run West on a true line between Secs. 26 & 35.
40.00	Set stone 18 x 10 x 8 for $\frac{1}{4}$ Sec. corner in ravine.
80.00	The corner to Secs. 26, 27, 34 & 35. Land, rolling. Soil, good 2nd rate.
<hr/>	
	North between Secs. 26 & 27. Variation 20° East
25.80	Ravine bears N.W.
40.00	Set stone 14 x 10 x 7 for $\frac{1}{4}$ Sec. corner.
80.00	Set post for corner to Secs. 22, 23, 26 & 27 in mound of earth with charred stake, pits &c., as per instructions. Land, rolling. Soil, good 2nd rate.
<hr/>	
	East on a random line between Secs. 23 & 26.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.86	Intersect N & S line at corner to secs. 23, 24, 25 & 26, from which corner, I run West on a true line between Secs. 23 and 26.
39.93	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.
79.86	The corner to Secs. 22, 23, 26 & 27. Land, gently rolling. Soil, 2nd rate.