

Subdivisions, T. 2 N., R. 32 E.

Chains		
	North between Secs. 32 & 33. Descend hill.	
37.75	Foot of hill. Enter field, bears N.W. & S.E.	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth, with charred stake, pits &c., as per instructions.	-250
59.00	Dry bed of Birch Creek, course N.W.	
74.00	Leave field, bears N.W. & S.E.	
80.00	Set stone 16 x 10 x 10 for corner to secs. 28, 29, 32 & 33. Land, gently rolling. Soil, 1st rate.	
<hr/>		
	East on a random line between Secs. 28 & 33.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	
80.00	Intersect 35 links South of corner to Secs. 27, 28, 33 & 34, from which I run S. 89° 45' W. on a true line between Secs. 28 & 33.	
.10	Dry bed of creek, course N.W.	
7.00	Ascend hill.	
30.00	Top of hill.	+400
39.88	Road bears N & S.	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.	
55.00	Descend hill.	
80.00	The corner to secs. 28, 29, 32 & 33. Land, gently rolling. Soil, 2nd rate.	-400
<hr/>		
	North between Secs. 28 & 29. Variation 19 $\frac{1}{2}$ ° East.	
	Ascend hill.	
40.00	Set stone 14 x 10 x 7 for $\frac{1}{4}$ Sec. corner.	
60.00	Top of hill.	
80.00	Set post for corner to Secs. 20, 21, 28 & 29 in mound of	