

Subdivisions, T. 2 N., R. 32 E.

Chains		
	earth with charred stake, pits &c., as per instructions.	+400
	Land, hilly.	
	Soil, 2nd rate.	
<hr/>		
	East on a random line between Secs. 21 & 28.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	
80.58	Intersect N & S line at corner to Secs. 21, 22, 27 & 28, from which I run	
	West on a true line between Secs. 21 & 28.	
	Descend hill.	
26.00	Foot of hill.	-300
31.50	Dry bed of creek, course North.	
40.29	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions. Ascend hill.	
79.90	Road bears N. E. & S.W.	
80.58	The corner to secs. 20, 21, 28 & 29.	+400
	Land, hilly.	
	Soil, good 2nd rate.	
<hr/>		
	North between Secs. 20 & 21.	
	Variation 20° East.	
	Descend hill.	
4.00	Road bears N.W. & S.E.	
32.75	Same road bears NE & S.W.	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.	
80.00	Set post for corner to Secs. 16, 17, 20 & 21 in mound of earth with charred stake, pits &c., as per instructions	-400
	Land, hilly.	
	Soil, 2nd rate.	
<hr/>		
	East on a random line between Secs. 16 & 21.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	
80.40	Intersect N & S line at corner to Secs. 15, 16, 21 & 22, from which I run	