

Subdivisions, T. 2 N., R. 32 E.

Chains	
	West on a true line between Secs. 16 & 21.
8.75	Road bears N.E. & S.W.
17.00	Enter brush, bears N & S.
19.00	Dry bed of creek, course North.
27.50	Leave brush, bears N & S.
40.20	Set stone 16 x 8 x 6 for $\frac{1}{4}$ Sec. corner.
80.40	The corner to Secs. 16, 17, 20 & 21.
	Land, rolling.
	Soil, 1st rate.
<hr/>	
	North between Secs. 16 & 17.
	Variation 20° East.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.
67.50	Dry bed of creek, course N.W.
77.00	Same creek, course N. 3° E..
80.00	Set post for corner to secs. 8, 9, 16 & 17 in mound of stone.
	Land, level creek bottom
	Soil, 1st rate.
	Timber, Cottonwood & Birch.
<hr/>	
	East on a random line between Secs. 9 & 16.
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
80.00	Intersect N & S line at corner to sections 9, 10, 15 & 16 from which I run
	West on a true line between Secs. 9 & 16.
9.80	Road bears S.W. & N.E.
17.00	Same Road, N.W. & S.E.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.
	Descend hill.
79.00	Dry bed of creek, course North.
80.00	The corner to Secs. 8, 9, 16 & 17.
	Land, rolling.
	Soil, 1st rate.