

Subdivisions, T. 2 N., R. 32 E.

Chains	
	North between Secs. 8 & 9. Variation 20° East.
1.00	Dry bed of creek, course N 5° W.
2.25	Enter field, bears E & W.
17.00	Leave field, bears NW & SE.
36.50	Road bears NW & SE.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.
49.00	Enter timber, bears E & W.
66.50	Umatilla River, 100 links wide, runs N.W. Road and bridge.
70.00	County Seat Umatilla Co. Court House bears East 400 links distant. Martin & Swift's store bears E. 6 chains distant. Old Emigrant bears E & W.
80.00	Set stone 24 x 12 x 10 for corner to secs. 4, 5, 8 & 9. Land, rolling. Soil, 1st rate. Timber, Cottonwood & Birch.
	East on a random line between Secs. 4 & 9.
40.00	Set temporary $\frac{1}{4}$ Sec. corner.
79.70	Intersect N & S line 70 links South of corner to Secs. 3, 4, 9 & 10, from which corner I run S. 89° 30' W. on a true line between Secs. 4 & 9.
35.00	Umatilla & Walla Walla Road bears NE & SW.
39.85	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.
79.70	The corner to Secs. 4, 5, 8 & 9. Land, rolling, sloping to the South. Soil, good 2nd rate.
	North on a random line between Secs. 4 & 5. Var. 20° East
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.
80.80	Intersect North boundary 74 links East of corner to Secs. 4 & 5, from which corner I run S. 0° 32' East on a true line between Secs. 4 & 5.