

Subdivisions, T. 2 N., R. 32 E.

Chains

North between Secs. 29 & 30.
 Variation 20° East.
 Descend.
 40.00 Set post for $\frac{1}{4}$ Sec. corner.
 58.00 Birch Creek. Dry bed. Course N.W.
 Enter field, bears N.W.
 77.00 Leave field, bears N.W. & S.E.
 80.00 Set stone 18 x 10 x 6 for corner to secs. 19, 20, 29 & 30.
 Land, rolling.
 Soil, 1st rate.
 Some Cottonwood and Birch timber on the creek.
 November 3rd, 1864.

East on a random line between Secs. 20 & 29.
 40.00 Set temporary $\frac{1}{4}$ Sec. corner.
 79.50 Intersect N & S line at corner to Secs. 20, 21, 28 & 29,
 from which corner I run
 West on a true line between Secs. 20 & 29.
 Descend hill.
 39.75 Set post for $\frac{1}{2}$ Sec. corner in mound of earth with charred
 stake, pits &c., as per instructions.
 79.50 The corner to secs. 19, 20, 29 & 30.
 Land, hilly.
 Soil, 2nd rate.

West on a random line between Secs. 19 & 30.
 40.00 Set temporary $\frac{1}{4}$ Sec. corner.
 87.74 Intersect West boundary at corner to secs. 19 & 30, from
 which corner I run
 East on a true line between Secs. 19 & 30.
 Descend hill.
 44.00 Enter field foot of hill, bears N & S.
 47.74 Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred
 stake, pits &c., as per instructions.
 60.00 Birch Creek (Dry) course N.W.

-250

-350