

Subdivisions T. 2 N., R. 32 E.

Chains		
70.00	Leave field bears N.W. & S.E.	
87.74	The corner to Secs. 19, 20, 29 & 30. Land, rolling. Soil, 1st rate.	
<hr/>		
	North between Secs. 19 & 20. Variation 22° East Ascend hill.	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.	
80.00	Set post for corner to Secs. 17, 18, 19 & 20 in mound of earth with charred stake, pits &c., as per instructions. Land, rolling. Soil, 2nd rate.	+300
<hr/>		
	East on a random line between Secs. 17 & 20.	
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.	
80.08	Intersect N & S line 30 links North of corner to Secs. 16, 17, 20 & 21, from which I run N. 89° 47' W. on a true line between Secs. 17 & 20. Ascend hill.	
20.00	Top of hill.	+200
40.04	Set post for $\frac{1}{4}$ Sec. corner in mound of earth with charred stake, pits &c., as per instructions.	
80.08	The corner to Secs. 17, 18, 19 & 20. Land, rolling. Soil, 2nd rate.	
<hr/>		
	West on a random line between Secs. 18 & 19.	
40.00	Set temporary $\frac{1}{4}$ Sec. corner.	
87.00	Intersect West boundary 40 links South of corner to Secs. 18 & 19, from which I run S. 89° 43' East on a true line between Secs. 18 & 19.	
.15	Leave Birch Creek. Dry bed. Runs North.	
11.00	Leave field, bears N & S.	