

Subdivisions, T. 2 N., R. 32 E.

Chains	
40.00	Set stone 20 x 14 x 7 for $\frac{1}{4}$ S. Cor.
43.40	Umatilla River, 58 links flows S.W.
80.00	To corner. Land, level. Soil, 1st rate.
North bet. Secs. 1 & 2.	
12.00	Umatilla river, 100 links E & W.
25.40	To boundary line of Indian reservation. Nov. 11, 1871.
West between Secs. 2 and 11.	
40.00	Set $\frac{1}{4}$ Sec. corner mound of earth.
51.00	Boundary Reservation.
North between Secs. 34 & 35.	
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. cor.
80.00	Set post and made mound of earth for cor. to Secs. 34, 35, 26 & 27. Land, rolling. Soil, 2nd rate. Good grass.
East on random bet. Secs. 26 and 35. Var. 20° 30' E.	
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
80.10	Intersected N & S line at cor. West on true line.
40.05	Set stone 18 x 14 x 7 for $\frac{1}{4}$ Sec. corner.
80.10	To corner. Land, rolling. Soil, 2nd rate. Good grass.
North bet. Secs. 26 & 27.	
26.00	Ravine bears N.W.
40.00	Set stone 17 x 10 x 9 for $\frac{1}{4}$ Sec. cor.