

Subdivisions, T 2 N., R. 32 E.

Chains	
	North between Secs. 14 & 15
40.00	Set post and made mound of earth for $\frac{1}{4}$ Sec. corner.
45.50	Tudie Willow, dry bed, N.W.
80.00	Set stone 20 x 17 x 14 for cor. to Secs. 14, 15, 10 & 11.
	Land, rolling.
	Soil, good 2nd rate.
<hr/>	
	East on random bet. Secs. 11 & 14.
	V. 21° E.
40.00	Set temporary $\frac{1}{4}$ Sec. cor.
80.40	Intersected N & S line at cor.
	West on true line.
40.20	Set post and made earth mound for $\frac{1}{4}$ S. cor.
80.40	To cor.
	Land, rolling.
	Soil, 2nd rate.
<hr/>	
	North bet. Secs. 10 & 11.
35.00	Enter bottom South of Umatilla River.
40.00	Set stone 20 x 15 x 9 for $\frac{1}{4}$ Sec. cor.
67.00	To the boundary of Indian Reservation.
<hr/>	
	North bet. Secs. 33 & 34.
24.00	Dry bed Howetome Ck.
68.00	To the Boundary of the Reservation.
	Land, rolling.
	Soil, 2nd rate.
<hr/>	
	East on random bet. Secs. 27 & 34.
	V. 20° E.
40.00	Set temporary $\frac{1}{4}$ S. cor.
80.00	Intersected N & S line 14 links N. of corner.
	N. 89° 54' W. on true line.
40.00	Set post and made mound of earth for $\frac{1}{4}$ S. cor.
80.00	To corner.
	Land, rolling. Soil, good.