

Subdivisions, T. 2 N., R. 32 E.

Chains	
80.00	Set post and made earth mound for cor. to Secs. 21,28,20 and 29. Land, rolling. Soil, good.
13.00	South bet. Secs. 28 & 29. To the Boundary of the Indian Reservation.
10.50	West bet. Secs. 20 & 29. To the Boundary of the Indian Reservation.
40.00	North bet. Secs. 20 & 21. V. 21° E.
80.00	Set post and made earth mound for $\frac{1}{4}$ Sec. corner. Set post and made mound of earth for cor. to Secs. 20,21, 16 and 17. Land, rolling. Soil, 2nd rate.
40.00	East on random bet. Secs. 16 & 21. V. 19°30' E.
80.50	Set temporary $\frac{1}{4}$ S. corner. Intersected N & S line at cor. W. on true line.
19.60	Dry bed of Howetome Ck. Course N.
40.25	Set stone 18 x 10 x 7 for $\frac{1}{4}$ S. cor.
80.50	To corner. Land, rolling. Soil, 2nd rate.
21.00	West bet. Secs. 17 & 20. To the Boundary of the Indian Reservation
40.00	North bet. Secs. 16 & 17. Set post and made mound of earth for $\frac{1}{4}$ Sec. cor.